

# SHEDS FOR SALE

Utility sheds are built at the Clark County Skills Center as part of the Construction Technology Program. They are built with quality in mind.

## Construction Materials

**Size:** 8' wide x 10' deep x 9'-4" tall with 6' - 4 1/2" headroom from subfloor to bottom of truss.

**Floor:** 2x6 floor joists with 3/4" plywood subfloor on two 4x4 pressure-treated skids.

**Walls:** 2x4 studs with 1/2" pre-primed T-1-11 siding.

**Trusses:** 2x4 trusses with vertical web and gussets.

**Roof:** 1/2" OSB sheathing with 15# felt and 3-tab comp. shingles.

**Trim:** 1x6 and 1x4 cedar trim boards.

**Door:** Single wide 4' door in 8' end.

- Sheds can be picked up and set up by you. They come in a "kit" form to be broken down and loaded onto your trailer. I need some advance notice if you wish to take advantage of this process. In this form, the shed does not have the roofing shingles.
- We can deliver, set up, and install a composition roof. Deliver dates are to be scheduled first come, first serve (once shed is paid for). Deliver during summer session only (June 25 thru July 13). Must be reasonable driving distance and safe area for students to work.

Shed quantities are limited. For current prices and more information, contact Bill Draper at (360) 604-1050 x-2148 or 360-910-0637 . If calling after hours, type in the extension after the message machine answers the call, and you will be routed into Bill's voice mail to leave your message or questions.